# Indian Standard

# METHOD OF TEST FOR DETERMINING SETTING TIME OF CONCRETE BY PENETRATION RESISTANCE

(Fifth Reprint MAY 1997)

UDC 666.972.015.5 : 539.533

© Copyright 1976

## BUREAU OF INDIAN STANDARDS MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG NEW DELHI 110002

# Indian Standard

# METHOD OF TEST FOR DETERMINING SETTING TIME OF CONCRETE BY PENETRATION RESISTANCE

Cement and Concrete Sectional Committee, BDC 2

Chairman

Representing

Dr H. C. VISVESVARAYA

Cement Research Institute of India, New Delhi

Members

Additional Director, Standards Railway Board (Ministry of Railways)

(B&S) (RDSO) DEPUTY DIRECTOR, STANDARDS

(B&S) (RDSO) (Alternate)

Dr A. S. Bhaduri National Test House, Calcutta

SHRIE. K. RAMACHANDRAN ( Alternate )

Indian Bureau of Mines, Nagpur CONTROLLER SHRI SURESH CHAND ( Alternate)

CHIEF ENGINEER Public Works Department, Government of Tamil DEPUTY (Buildings) Nadu

DEPUTY CHIEF ENGINEER

(IRRIGATION & DESIGNS) (Alternate)

DR G. S. DHILLON Irrigation & Power Research Institute, Amritsar RESEARCH OFFICER ( CC )( Alternate )

DIRECTOR Central Road Research Institute (CSIR) New Delhi

DR R. K. GHOSH ( Alternate ) DIRECTOR (CSMRS)

Central Water Commission, New Delhi DEPUTY DIRECTOR (CSMRS) (Alternate)

ENGINEER-IN-CHIEF Central Public Works Department, New Delhi

SUPERINTENDING ENGINEER.

DELHI CENTRAL CIRCLE 2 ( Alternate )

SHRIK, H. GANGWAL Hyderabad Products Ltd. Asbestos Cement Hvderabad

SHRI K. C. GHOSAL DR R. K. GHOSH

Alokudyog Services Ltd, New Delhi Indian Roads Congress, New Delhi Engineer-in-Chief's Branch, Army Headquarters Brig Harish Chandra SHRI G. R. MIRCHANDANI ( Alternate )

Dr R. R. HATTIANGADI

The Associated Cement Companies Ltd, Bombay SHRI P. J. JAGUS ( Alternate )

DR IOBAL ALI

Engineering Research Laboratories, Hyderabad SHRI M. T. KANSE Directorate General of Supplies & Disposals, New Delhi

(Continued on page 2)

## Copyright 1976

## BUREAU OF INDIAN STANDARDS

This publication is protected under the Indian Copyright Act (XIV of 1957) and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

(Continued from page 1)			
Members	Representing		
Shri S. L. Kathuria Shri S. R. Kulkarni Dr Mohan Rai	Roads Wing (Ministry of Shipping & Transport) M. N. Dastur & Co (Pvt) Ltd, Calcutta Central Building Research Institute (CSIR). Roorkee		
DR S. S. REHSI ( Alternate ) SHRI ERACH A. NADIRSHAH SHRI K. K. NAMBIAR PROF G. S. RAMASWAMY	Institution of Engineers (India), Calcutta In personal capacity ('Ramanalaya' 11 First Crescent Park Road, Gandhinagar, Adyar, Madras) Structural Engineering Research Centre (CSIR), Roorkee		
DR N. S. BHAL (Alternate) DR A. V. R. RAO SHRI K. S. SRINIVASAN (Alternate) SHRI R. V. CHALAPATHI RAO SHRI S. ROY (Alternate) SHRI T. N. S. RAO SHRI S. R. PINHEIRO (Alternate) SECRETARY DEPUTY SECRETARY (I) (Alternate) SHRI G. B. SINGH SHRI G. B. SINGH SHRI J. S. SINGHOTA SHRI T. C. GARG (Alternate) SHRI K. A. SUBRAMANIAM SHRI P. S. RAMACHANDRAN (Alternate) SHRI A. V. RAMANA (Alternate) SHRI B. T. UNWALLA SHRI T. M. MENON (Alternate) SHRI D. AJITHA SIMHA,	National Buildings Organization, New Delhi  de) Geological Survey of India, Calcutta  Gammon India Ltd, Bombay  Central Board of Irrigation & Power, New Delhi  ate) Hindustan Housing Factory Ltd, New Delhi  e) Beas Designs Organization, Nangal Township  India Cements Ltd, Madras  ternate) Dalmia Cement (Bharat) Ltd, New Delhi		
Director (Civ Engg)	,		
	Secretary		
SHRI M. N. NEELAKANDHAN Assistant Director ( Civ Engg ), ISI			
Concrete Subcommittee, BDC 2:2			
SHRI C. R. ALIMCHANDANI SHRI M. C. TANDON ( Alternate ) DEPUTY DIRECTOR, STANDARDS ( B & S ) ( R D SO ) A S S I S T A N T DIRECTOR STANDARDS ( M/C ) ( R D SO ) DIRECTOR DIRECTOR ( C & MDD ) DEPUTY DIRECTOR ( C & MDD SHRI V. K. GHANEKAR  SHRI A. S. PRASADA RAO ( Alternate )	Railway Board (Ministry of Railways)  ( Alternate ) Engineering Research Laboratories, Hyderabad Central Water Commission, New Delhi ) (Alternate) Structural Engineering Research Centre (CSIR), Roorkee		
(1000)	(Continued on page 8)		

# Indian Standard

# METHOD OF TEST FOR DETERMINING SETTING TIME OF CONCRETE BY PENETRATION RESISTANCE

### O. FOREWORD

- **0.1** This Indian Standard was adopted by the Indian Standards Institution on 8 July 1976, after the draft finalized by the Cement and Concrete Sectional Committee had been approved by the Civil Engineering Division Council.
- 0.2 Information obtained from the penetration resistance test for setting of concrete can provide useful guidance to the engineer at site regarding removal of formwork, maximum permissible time lapse between placement of successive layers of concrete and such other operations, where assessment of the degree of hardening of the concrete is necessary. The method may be used for determining the effects of variables, such as temperature, cement, concrete mix proportions and admixtures, upon the time of setting and hardening characteristics of concrete. It may be used as a part of performance specifications to determine compliance with specified time of setting requirements and will also be useful in the laboratory for comparative studies of above aspects.
- 0.2.1 The method is suitable only for those cases where required information on the above aspects can be obtained from the tests on the mortar fraction of the concrete. Since the hardening of concrete is a gradual process, any definition of setting time will necessarily be arbitrary. The temperature of storage of specimens employed in this test is to be selected by the user.
- **0.3** The Sectional Committee responsible for the preparation of this standard has taken into consideration, the practices followed in this country in conducting the test for determining setting time of concrete by penetration resistance. Due weightage has also been given to the need for international co-ordination among the standards and practices prevailing in different countries of the world.
- **0.4** For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a test or analysis, shall be rounded off in accordance

with IS: 2-1960\*. The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard.

#### 1. SCOPE

- 1.1 This standard covers the method for determining the setting time of concrete with slump greater than zero, by testing mortar sieved from the concrete mixture.
- 1.2 In this method of test, the initial setting time and the final setting time are the time intervals required for the mortar sieved from the concrete mixture to reach the prescribed penetration resistance after the initial contact of cement and water.

#### 2. TERMINOLOGY

- 2.0 For the purpose of this standard, the following definitions shall apply.
- 2.1 Initial Setting Time The elapsed time, after initial contact of cement and water, required for the mortar (sieved from the concrete) to reach a penetration resistance of 3.43 N/mm<sup>2</sup> (35 kgf/cm<sup>2</sup>).
- 2.2 Final Setting Time The elapsed time, after initial contact of cement and water, required for the mortar (sieved from the concrete) to reach a penetration resistance of 26.97 N/mm<sup>2</sup> (275 kgf/cm<sup>2</sup>).

#### 3. APPARATUS

3.1 Containers for Mortar Specimens—Rigid, watertight, non-absorptive, non-oiled containers, either cylindrical or rectangular in cross-section, with minimum lateral dimension 150 mm and height at least 150 mm.

Note — The container for the mortar from the concrete mixture shall provide enough mortar surface for the undisturbed reading of penetration resistance.

3.2 Penetration Resistance Apparatus — Spring reaction-type apparatus, graduated from 50 N (5 kgf) to 600 N (60 kgf) in increments of 10 N (1 kgf) or less; or hydraulic reaction-type apparatus with pressure gauge of 700 to 900 N (70 to 90 kgf) capacity, graduated in increments of 10 N (1 kgf) or less. Indications of actual needle loads by these apparatus shall be accurate to 10 N (1 kgf). Removable needles of 645, 323, 161, 65, 32 and 16 mm² bearing areas shall be provided. Each needle shank shall be scribed peripherally at a distance of 25 mm above the bearing face. The length of the 16 mm² needle shall be not more than 90 mm to minimize bending.

Note — The spring reaction-type apparatus shall be recalibrated periodically.

<sup>\*</sup>Rules for rounding off numerical values (revised).

- 3.3 Pipette Pipette or suitable instrument for drawing off free water from the surface of the test specimens.
- 3.4 Tamping Rod Round, straight, steel rod 16 mm in diameter and approximately 600 mm in length, having the tamping end rounded to a hemispherical tip, of 16 mm diameter.

#### 4. PREPARATION OF MORTAR SPECIMENS

- **4.1** From the concrete mixture under test, select a representative sample of concrete of sufficient volume to provide enough mortar to fill the test container, or containers, to a depth of at least 140 mm.
- 4.2 Remove essentially all of the mortar from the sample of concrete by sieving it through a 4.75-mm IS sieve onto a non-absorptive surface.
- 4.3 Thoroughly remix the mortar by hand on the non-absorptive surface and place it in the container, or containers in layers of 50 mm each, and compact by rodding each layer. Rod the specimen by means of the tamping rod held so as to penetrate the mortar with the round end. Rod the mortar once for each 6.5 cm² of top surface area of the specimen and distribute the strokes uniformly over the cross-section of the specimen. After completion of the rodding, tap the sides of the containers lightly with the tamping rod to close voids left by the tamping rod and to further level the surface of the specimen. Upon completion of specimen preparation, the mortar surface shall be at least 13 mm below the top edge of the container to provide space for the collection and removal of bleeding water and to avoid contact between the mortar surface and the protective covering specified in 5.1.

#### 5. STORAGE OF MORTAR SPECIMENS

5.1 Store and maintain the specimens at the temperature, selected for testing the specimens. To prevent excessive evaporation of moisture, keep the specimens covered and protected with a suitable tight-fitting, water-impermeable cover for the duration of the test, except when bleeding water is being removed or penetration tests are being made. The specimens shall be shielded from the sun.

## 6. NUMBER OF SPECIMENS

6.1 At least three separate batches shall be made for each test condition. One rate of hardening test shall be made on each batch. An equal number of batches for each condition shall be made on any given day. When it is impossible to make at least one test for each variable on a given day, the mixing of the entire series of batches shall be completed in as few days as possible and one of the mixtures shall be repeated each day as a standard of comparison.

#### 7. PROCEDURE

- 7.1 Remove bleeding water from the surface of the mortar specimens just prior to making a penetration test by means of a pipette or a suitable instrument. To facilitate collection of bleeding water, tilt the specimen carefully to an angle of about 12° from the horizontal by placing a block under one side 2 minutes prior to removal of the bleeding water.
- 7.2 Insert a needle of appropriate size, depending upon the state of hardening of the mortar, in the penetration resistance apparatus and bring the bearing surface of the needle into contact with the mortar surface. Gradually and uniformly apply a vertical force downward on the apparatus until the needle penetrates the mortar to a depth of 25 mm as indicated by the scribe mark. The time required to penetrate to the 25 mm depth shall be approximately 10 seconds. Record the force required and the time of application, measured as elapsed time after initial contact of cement and water. In subsequent penetration tests take care to avoid areas where the mortar has been disturbed by previous tests. The clear distance between two needle impressions shall be at least two diameters of the needle being used, but not less than 13 mm. The clear distance between any needle impression and the side of the container shall be not less than 25 mm.
- 7.3 Make penetration tests at hourly intervals for normal mixtures and normal temperatures, the initial test being made after an elapsed time of 3 to 4 h. For accelerated mixtures or high temperatures, it may be advisable to make the initial test after an elapsed time of 1 or 2 h and subsequent tests at  $\frac{1}{2}$  h intervals. For low-temperature conditions or retarded concrete mixtures, the initial penetration test may be deferred for an elapsed time of 4 to 6 h, and perhaps longer. Subsequent tests may be made at intervals of 1 h, unless the rate of increase in penetration resistance indicates that shorter intervals are desirable.
- 7.4 Not less than six penetration resistance determinations shall be made in each rate of hardening test and the time intervals between penetration resistance determinations shall be such as to give a satisfactory rate of hardening curve, as indicated by equally spaced points. Continue the tests until one penetration resistance of at least 26.97 N/mm² (275 kgf/cm²) is reached.

#### 8. CALCULATION

**8.1** Calculate the penetration resistance, in  $N/mm^2$  (kgf/cm<sup>2</sup>), as the force required to cause a 25 mm depth of penetration of the needle divided by the area of the bearing face of the needle.

#### 9. PRECISION

9.1 The range of three results of properly conducted tests by the same operator with the same machine using similar materials on different days

shall not exceed 84 minutes, and the average setting times for two sets of tests each consisting of three similar batches shall not depart more than 20 minutes from the average of the two.

### 10. REPORT

- 10.1 The report shall include the following:
  - a) Data on Concrete Mixture Type and proportions of cement, fine aggregate, coarse aggregate (including maximum size and grading of aggregates), and the ratio of net water content to cement content;
  - b) Name, nature, and percentage of active ingredients by mass of cement, of any admixture used;
  - c) Air content of fresh concrete and method of determination;
  - d) Consistency of concrete as determined by the slump or other test for consistency;
  - e) Temperature of mortar after sieving;
  - f) Record of ambient temperature during the test period; and
  - g) Date of test.
- 10.2 Curves For each variable and condition of concrete as specified in 6, the results from each of three or more rate of hardening tests shall be plotted separately, showing penetration resistance in N/mm² (kgf/cm²) as the ordinate and elapsed time in hours and minutes as the abscissa, where 3.5 MN/m² (35 kgf/cm²) and 1 hour are represented by not less than 13 mm.
- 10.3 Time of Setting Times of initial and final setting as defined in 2.1 and 2.2 shall be calculated by averaging the clapsed times, determined from the curves plotted in accordance with 10.2 at which penetration resistances of 3.43 N/mm<sup>2</sup> (35 kgf/cm<sup>2</sup>) and 26.97 N/mm<sup>2</sup> (275 kgf/cm<sup>2</sup>) respectively, are reached. Times of setting shall be reported in hours and minutes to the nearest minute.

( Continued from page 2 )

#### Members

#### Representing

SHRI K. C. GHOSAL BRIG HARISH CHANDRA MAJ S. G. VOMBATKERE ( Alternate ) SHRI J. S. HINGORANI SHRI A. P. REMEDIOS ( Alternate ) SHRI P. J. JAGUS T SHRI M. R. VINAYAKA (Alternate) SHRI S. R. KULKARNI SHRI B. C. PATEL ( Alternate ) SHRI G. C. MATHUR SHRI G. T. BHIDE ( Alternate ) Dr P. K. Mohanty DR R. S. PRASAD ( Alternate ) SHRI K. K. NAMBIAR DR M. L. PURI SHRI N. S. RAMASWAMY SHRI R. P. SIKKA ( Alternate ) SHRI R. V. CHALAPATHI RAO SHRI S. ROY ( Alternate ) SHRI T. N. S. RAO SHRI S. R. PINHEIRO ( Alternate ) SUPERINTENDING ENGINEER (CENTRAL CIRCLE No. 2) SHRI S. G. VAIDYA ( Alternate ) SUPERINTENDING ENGINEER (Design Circle, PW) Dr C. A. Taneja SHRI B. S. GUPTA ( Alternate )
SHRI N. M. THADANI SHRI B. T. UNWALLA SHRI T. M. MENON ( Alternate )

Dr H. C. VISVESVARAYA

DR A. K. MULLICK ( Alternate )

Alokudyog Services Ltd, New Delhi
Engineer-in-Chief's Branch, Army Headquarters
nate)
Associated Consulting Services, Bombay

The Associated Cement Companies Ltd, Bombay
ate)
M. N. Dastur & Co Pvt Ltd, Calcutta

National Buildings Organization, New Delhi

In personal capacity ( 'Ramanalaya' 11 First Crescent Park Road, Gandhinagar, Adyar, Madras) Central Road Research Institute ( CSIR ), New Delhi Roads Wing ( Ministry of Shipping & Transport )

Geological Survey of India, Calcutta

Tor-Isteg Steel Corporation, Calcutta

Gammon India Ltd, Bombay

Central Public Works Department, New Delhi

Public Works and Housing Department, Government of Maharashtra, Bombay Central Building Research Institute (CSIR), Roorkee

In personal capacity (82, Marine Drive, Bombay)
The Concrete Association of India, Bombay

Cement Research Institute of India, New Delhi

#### **BUREAU OF INDIAN STANDARDS**

#### Headquarters:

Central Laboratory:

**LUCKNOW 226001** 

BANGALORE 560002

Patliputra Industrial Estate, PATNA 800013

THIRUVANANTHAPURAM 695034

T. C. No. 14/1421, University P. O. Palayam,

Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002

Telephones: 323 0131, 323 3375, 323 9402

Fax: 91 11 3234062, 91 11 3239399, 91 11 3239382

Community.	rolephone
Plot No. 20/9, Site IV, Sahibabad Industrial Area, SAHIBABAD 201010	8-77 00 32
Regional Offices:	
Central: Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002	323 76 17
*Eastern: 1/14 CIT Scheme VII M, V.I.P. Road, Maniktola, CALCUTTA 700054	337 86 62
Northern: SCO 335-336, Sector 34-A, CHANDIGARH: 160022	60 38 43
Southern: C.I.T. Campus, IV Cross Road, CHENNAI 600113	235 23 15
†Western : Manakalaya, E9 Behind Marol Telephone Exchange, Andheri (East) MUMBAI 400093	, 832 92 95
Branch Offices:	
'Pushpak', Nurmohamed Shaikh Marg, Khanpur, AHMEDABAD 380001	550 13 48
‡Peenya Industrial Area, 1st Stage, Bangalore-Tumkur Road, BANGALORE 560058	839 49 55
Gangotri Complex, 5th Floor, Bhadbhada Road, T. T. Nagar, BHOPAL 462003	55 40 21
Plot No. 62-63, Unit VI, Ganga Nagar, BHUBANESHWAR 751001	40 36 27
Kalaikathir Buildings, 670 Avinashi Road, COIMBATORE 641037	21 01 41
Plot No. 43, Sector 16 A, Mathura Road, FARIDABAD 121001	8-28 88 01
Savitri Complex, 116 G. T. Road, GHAZIABAD 201001	8-71 19 96
53/5 Ward No. 29, R. G. Barua Road, 5th By-lane, GUWAHATI 781003	54 11 37
5-8-58C, L. N. Gupta Marg, Nampally Station Road, HYDERABAD 500001	20 10 83
E-52, Chitaranjan Marg, C-Scheme, JAIPUR 302001	37 29 25
117/418 B, Sarvodaya Nagar, KANPUR 208005	21 68 76

*Sales Office is at 5 Chowringhee Approach, P. O. Princep Street,	
CALCUTTA 700072	27 10 85
†Sales Office is at Novelty Chambers, Grant Road, MUMBAI 400007	309 65 28
‡Sales Office is at 'F' Block, Unity Building, Narashimaraja Square,	222 39 71

Seth Bhawan, 2nd Floor, Behind Leela Cinema, Naval Kishore Road,

NIT Building, Second Floor, Gokulpat Market, NAGPUR 440010

Institution of Engineers (India ) Building, 1332 Shivaji Nagar, PUNE 411005

Telegrams: Manaksanstha (Common to all Offices)

Telephone

23 89 23

26 23 05

6 21 17

52 51 71

32 36 35